
# POTTER DRIVE, CREIGHTON DRIVE, SOUTH AND MAIN STREETS RECONSTRUCTION LOYALIST TOWNSHIP





# **INDEX**

N.T.S.

	COVER SHEET
GEN	GENERAL PLAN
PP01	MAIN STREET (CTY RD 2) PLAN AND PROFILE STA. 1+000.00 TO 1+160.00
PP02	MAIN STREET (CTY RD 2) PLAN AND PROFILE STA. 1+160.00 TO 1+320.00
PP03	MAIN STREET (CTY RD 2) PLAN AND PROFILE STA. 1+300.00 TO 1+440.00
PP04	POTTER DRIVE PLAN AND PROFILE STA. 2+000.00 TO 2+160.00
PP05	SOUTH STREET W PLAN AND PROFILE STA. 3+000.00 TO 3+190.00
PP06	CREIGHTON DRIVE PLAN AND PROFILE STA. 4+000.00 TO 4+171.00
G1	GRADING PLAN 1
G2	GRADING PLAN 2
STM	PROPOSED CATCHMENT AREAS
ER	SEDIMENT AND EROSION CONTROL AND TREE PRESERVATION PLAN
D1	DETAILS 1 TYPICAL CROSS SECTIONS I
D2	DETAILS 2 TYPICAL CROSS SECTIONS II
D3	DETAILS 3 GRADING DETAILS
D4	DETAILS 4 WATER & SEWER DETAILS
D5	DETAILS 5 WATER & SEWER DETAILS
D6	DETAILS 6 MISCELLANEOUS DETAILS
D7	DETAILS 7 MISCELLANEOUS DETAILS
D8	LINE PAINTING PLAN
D9	PEDESTRIAN TRAFFIC SIGNALS DETAIL

#### While undertaking clearing, demolition, excavation or construction the Owner and their contractors shall be vigilant for the potential presence of underground fuel tanks, potentially contaminated soils or groundwater, buried wastes or abandoned water wells. If any of the above are encountered or suspected, the Owner shall ensure that: Loyalist Township shall be advised if contaminates or wastes have been discovered or suspected; Any soil or groundwater contamination encountered is remediated to applicable standards as defined in O. Reg. 153/04 or as revised; Any wastes generated by site clean-ups are managed in accordance with applicable laws and standards; Any abandoned fuel tanks encountered are decommissioned in accordance with applicable Any unused water wells (drilled or dug) are properly abandoned in accordance with Accordance with O. Reg. 903-Wells or as revised; If it appears likely that contamination extends beyond the boundaries of the subject property, the Owner notifies the local office of the Ministry of the Environment and the Loyalist Township's Engineering Division; Construction wastes are not to be buried within the property that is the subject of this Agreement, and That the Owner and their contractors report all spills to the Ministry of the Environment's Spills Action Centre (1-800-268-6060) and to the Municipality (613-386-7351, ext. 116) SEDIMENT AND EROSION CONTROL NOTES All erosion and sediment controls shall be installed prior to construction and monitored and maintained by the Contractor throughout the construction process, until all disturbed areas have been revegetated, then the temporary sediment and erosion control measures must be removed once the site has been stabilized and or the site works are complete. All erosion and sediment control measures shall be inspected after each rainfall to the satisfaction of Loyalist Township and the CRCA. Any disturbed area not scheduled for further construction within forty-five (45) days will be provided with a suitable temporary mulch and seed cover within seven (7) days of completion of that particular phase of construction. Regardless of site specific items detailed on the plans, the Contractor shall install erosion control measures to suit the proposed work methods controlling sediment runoff from discharging offsite prior to any disturbance. Following construction, disturbed areas, as well as proposed grassed and vegetated surfaces, shall be reinstated as soon as practical. The placement of surplus fill be placed and/or temporarily stored in accordance with the Loyalist Township Fill By-laws as amended whether within the draft plan of subdivision or elsewhere in the Township. Temporary fill sites within the Plan of Subdivision will require the approval of the Township. Fill locations, side slopes, elevations as per the Approved Drawings. Restoration to be completed during the final phase of construction. All roads used to access the subdivision shall be kept clean to the satisfaction of the Engineering Manager. All works to be installed and tested in accordance with current Lovalist Township Development Guidelines & Technical Standards, manufacturer requirements and Ontario Provincial Standard (OPS) Specifications and Drawings unless specified otherwise. Where applicable, OPS municipal Specifications as amended shall be utilized including OPSS.MUNI 100 unless specified otherwise DRAWING PP01

No blasting allowed on this project

All pipe material to be CSA certified.

Granular depths as per cross sections.

OPSD 600.011 on Main Street.

352 and 353, 1301, 1302 and 1350.

with the Ontario Traffic Manual

be substituted for steel beam guide rails.

surround and weep holes as per detail provided.

Aggregates - Granular A and B. OPSS 1010 must be adhered to.

Commercial Relations (416) 326-8392, shall be notified immediately.

8. Refer to Geotechnical Investigation dated January 2024 by Malroz Engineering.

Provincial Standard Specifications, and the Geotechnical Investigation.

Curb radii to be 12.0m to front of curb unless noted otherwise.

Main Street / County Road 2 asphalt to be SP19 base and SP12.5 surface.

Road subgrade (including fill sections) to be constructed in accordance with current Loyalist

Township Site Plan Design and Development Guidelines and Technical Standards, Ontario

Hot mix asphalt to depth as per cross section. For Main Street (County Road 2) Hot Mixed

Hot Laid Asphaltic Concrete as per OPSS 1151. Superpaye Mix designs shall contain a

with a performance grade of PG58H-34. Normal crossfall on all roads to be 2%. Wear

the completion of a closed circuit T.V. inspection of both the storm and sanitary sewer

All materials for sidewalks shall conform to O.P.S.S. 1002, concrete is to conform to

Sidewalk thickness shall be increased to 200mm for all entrances other than urban

0.45 maximum water/cement ratio, 75mm maximum slump, white pigmented curing

Boulevard slope shall be a minimum of 2% and a maximum of 8% within the ROW.

Road catchbasins in areas that do not have subdrains - to have a drainage interception

Polystyrene Adjustment Units or approved equivalent as per OPSD 704.012 and in

accordance with OPSS 1854. Adjustment units and adhesives are to be installed as per

All storm and sanitary structures shall be adjusted to grade by use of Strataworks Expanded

manufacturers specifications. Appropriate angled forms are to be utilized to match surface

All signage including those requiring relocation by the works shall be installed in accordance

Dead end barricades to be as per OPSD 912.532 with Wa8 sign. Concrete barricades may

Boulevards to be finished with 100 mm of topsoil and nursery sod unless noted

otherwise Ditches to have a maximum side slope of 3:1 unless noted otherwise

Maintenance holes must contain ladder rungs within 450mm from the top.

O.P.S.S. 1350 and are to be constructed as per O.P.S.S. 351. Sidewalks are to be a

minimum of 1500 mm wide, 125 mm thick with 125 mm compacted Granular A bedding.

at intersections or road crossings shall be installed in accordance with OPSD 310.030.

Concrete shall be 32 Mpa minimum 28 day strength, 19mm coarse aggregate nominal

residential. Sidewalk design shall be as per O.P.S.D. 310.010 and 310.050. Sidewalk ramps

maximum size, 6.0% to 8.0% air content, normal portland type cement as per OPSS 1301,

compound as per OPSS 1315. Concrete materials and production as per OPSS 350, 351,

minimum of 4.8% performance grade asphalt (PGAC) for SP19 and 5.6% PGAC for SP9.5

course asphalt shall not be placed in the same calendar year as the binder course or before

Concrete Curb and Gutter shall be semi-mountable type OPSD 600.020 and 600.060. Install

curb at catchbasin to OPSD 610.010. Where specified barrier curb as per OPSD 600.040 or

14. Traffic control to be as per Ontario Traffic Manual Book 7. Soils are to be managed and reused in accordance with O. Reg. 406/19. the Contractor Existing trees to be retained and protected as directed by the Engineer. Tree protection shall shall use suitable soil generated from excavation activities as fill onsite before moving it from be installed along the drip line of all trees to be retained prior to construction. the project area. ensure that temporary stockpiles are located and protected In the event that buried archaeological remains be found on the property during construction appropriately unsuitable materials, deleterious materials, asphalt, concrete, pipes, etc.or excess soil shall be tested to determine the Regulation 347 waste class and removed from activities, the Ministry of Citizenship, Culture and Recreation shall be notified immediately. In the event that human remains are encountered during construction, the Ministry of the project area and safely transported by a licensed hauler and disposed offsite to a licensed receiver in accordance with OPSS 180. Citizenship, Culture and Recreation shall be notified immediately and the Registrar or Deputy Registrar of the Cemeteries Regulation Unit of the Ministry of Consumer and Hydro poles may require temporary support due to proximity to services. The use of a trench box may be required due to the proximity of services to hydro poles.

to be reinstated with 100mm topsoil and sod at no extra cost

<u>SEWERS</u>

Pipe bedding and cover shall conform to OPSD 802 series. Bedding and cover shall be Granular "A". All pipe and fittings supplied shall carry CSA certification to the appropriate CSA standard

sewer grade. The following pipe shall be used for sewers: Sanitary sewer pipe materials as per: a. Reinforced concrete pipe per OPSS 1820 according to CSA A257.2 Class 65-D with rubber gaskets or;

Areas in the municipal R.O.W. damaged due to tracked equipment or construction traffic are

b. Type PSM polyvinyl chloride (PVC) pipe with elastomeric gasket per OPSS 1841 and CSA B182.2 M1990. Profile type pipe such as those meeting CSA 182.4 and CSA 182.6 shall not be used for sanitary sewer applications.

Sanitary Mains to be DR 35 pipe d. Sanitary Laterals to be DR 28 pipe

a. Watermains shall be C900 DR18 Class 235 psi, Molecularly Oriented Polyvinyl Chloride (PVCO) pipe to be as per AWWA C909. Ductile watermain pipe not permitted, ductile Storm sewer pipe materials as per: fittings permitted. Other pipe materials may be accepted by the Township at the sole Reinforced concrete pipe per OPSS 1820 according to CSA A257.2 Class 65-D with discretion of the Engineering Manager based on the acceptance of technical specification rubber gaskets or for that material.

ii. Type PSM polyvinyl chloride (PVC) pipe with elastomeric gasket per OPSS 1841 and CSA B182.2 M1990. (i) Mains - DR 35 pipe (ii) Storm Laterals - DR 35 pipe Profile Polyvinyl Chloride (PVC) pipe with elastomeric gasketed bell and spigot type joints meeting CSA 182.4 and having a minimum stiffness of 320 kPa may be used for storm sewer applications. iv. ADS N-12 ST/WT sizes 100mm to 750mm corrugated dual-wall High Density

Polyethylene (HDPE) pipe with elastomeric gasketed bell and spigot type joints meeting CSA 182.8 and OPSS 1840, and having a minimum stiffness of 320 kPa. Sewers shall be tested for deflection as per OPSS 410. Sewers shall be flushed immediately prior to the closed circuit TV inspection. Where a clearance between pipe or conduit crossings of 300mm or less cannot be avoided.

there shall be concrete encasement or non-shrink backfill of the crossing extending one metre in each direction on each pipe. Sanitary sewer manhole frame and cover to OPSD 401.01 Type 'A' unless otherwise noted'. Storm sewer manhole frame and cover to OPSD 401.01 Type 'B' unless otherwise noted. Catchbasin leads to be 300 mm unless noted otherwise

Catchbasins to OPSD 705.010 with frame and cover to OPSD 400.010 (rear yard catchbasin OPSD 400.020) with 600 mm sump unless otherwise noted. Install Geotextile fabric under all catchbasin grates until construction phase is complete. All manhole and catchbasin grate elevations are approximate and are subject to adjustment

Sanitary sewer are not to be used for dewatering purposes. All sanitary sewer structure joints shall be sealed by a waterproof membrane such as Blueskin or approved equivalent, a minimum of 300mm on center of the joint allowing 150mm either side of all joints.

12. Water and sewer services and foundation drains may be laid in the same trench subject to the provisions of Ontario Building Code.

16. Sanitary laterals to have a minimum 2.1m of cover at property line and a maximum 2.5m

All laterals shall be run perpendicular into the property line or aimed towards the house. If

18. Sanitary laterals are to extend 1.5 metres beyond the property line. The bell end is to remain

on the last piece of pipe leading up to the property line and shall be 4m in length.

b. Watermains shall be restrained as per OPSS 441 and the pipe manufacturer

instructed in writing by the Engineer.

accordance with ANSI/AWWA C111/A21.11.

c. Watermains shall not be used as an electrical ground in new buildings.

prior approval of the Engineer

mechanical restraints.

sweeps are required to line up the service they should be located on the municipal side of

i) Pipe and joint restraint shall comply with OPSD 1103.010/1103.020 or as set out

herein. Assume a soil bearing strength of 100 - 199 kPa unless otherwise

iii) Mechanical joint restraints may be used in place of thrust blocks subject to the

v) The number of joints requiring mechanical thrust restraint shall be set by the

vi) All joint restraint devices for PVC shall carry a water working pressure rating

equivalent to the full rated pressure of the PVC pipe on which they will be installed,

meet or exceed the requirements of Uni-B-13-94 or ASTM F1674. Restraint devices

shall be manufactured of high strength ductile iron, ASTM A 536, Grade 65-45-12.

connecting tracer wires Dryconn Waterproof Direct Bury connecter shall be utilized or an

Bolts and connecting hardware shall be of high strength low alloy material in

d. All non-metallic watermains and water services shall require tracer wire. Tracer wire shall

be strapped to the watermain every 3 meters and 2 meters along services. When

with a minimum factor of safety of 2:1 in any nominal pipe size. In addition, they shall

ii) Thrust blocks shall be installed as per OPSD 1103.010 and 1103.020. All

hydrant's, bend's, tee's, and dead ends require concrete thrust blocks.

iv) All dead ends, bends, valves, fittings, hydrants, and reductions shall have

Sanitary laterals shall be 125mm PVC SDR 28, green in colour.

cover at the property line unless noted otherwise.

<u>Watermain</u>

requirements at a minimum.

f. Tracer wire shall be installed as per the details on the detail sheet. g. Install one 7.7 kg Magnesium anode on every valve, hydrant and fitting, all thermite weld connections shall be coated with Roybond 747 primer and Royston "handy cap" or 13. The horizontal separation between each service shall be 0.5m. All other utility services shall approved equivalent. Install one Zinc anode on every 1000 m of tracer wire. Anodes shall be separated 2.5m from water and sewer services measured from edge of structure. be placed at least 1.0m away from the water system and other anodes. Install 7.7 kg 14. Building sewers from the building line to the main shall be laid at a minimum of 2% from the Magnesium anode on existing metallic watermains when they are exposed for new building line to the main sewer. The first 40 building sanitary services connected to 200mm services in addition to the service anodes. main shall be set above the spring line of the sewer main with a proper "Y" fittings and with h. If existing Anodes are encountered replace with 7.7 kg Magnesium anode. ong radius bends. Building sewers connected to larger mains may be by a tee connection with the side of the tee rotated at between 22 1/2 degrees and 45 degrees above horizontal.

i. Service taps will include stainless steel saddle or pre-manufactured tee as recommended by pipe manufacturer and as approved by the Township. The minimum depth of cover for all watermains shall be 1.7m, or as required by the Engineering Manager or MOE. Watermain shall be evenly graded to avoid localized high

e. Tracer wire to be 12 gauge 600V TWU CSA No. 75 stranded copper and plastic coated or

k. Watermains shall cross above sewers with sufficient clearance to allow for proper bedding and structural support of the watermain and sewer main. Where it is not possible for the watermain to crossabove the sewer, the watermain shall pass under the sewer providing a minimum of 500mm vertica Iseparation between the invert of the sewer and the crown of the watermain. The length of water pipe shall be centered on at the point of crossing so that the joints will be equal distance from the sewer.

Valves shall be left hand open (counter clockwise). Valve boxes shall be Bibby or AVK type or equivalent resilient wedge valve all having an inside screw, non-rising spindle, with a 50mm square opening nut and mechanical joint and conform to ANSI/AWWA C509. Where a resilient wedge valve is not available a by-pass shall be installed. m. Contractor is to obtain confirmation of valve opening orientation in writing from the

Township prior to ordering valves. n. A minimum of 48 hours written notice is required to customers prior to any scheduled shut-down of the water distribution system. A Township approved notice shall be hand delivered to all affected customers.

o. All new watermains under construction and temporary water services shall be tested in accordance with OPS and "Loyalist Township Watermain Testing & Disinfection Guidelines - as amended". p. New watermains shall not be connected to the existing system without backflow

prevention until such time as all testing has been completed in accordance with Loyalist ownship - Water Distribution System - New Construction - Testing Requirements. q. Contractor to submit to Loyalist Township a "Watermain Testing, Disinfection and Final Connection Plan" for review and approval prior to testing and disinfecting of the

Fire hydrants

a. Hydrant locate station to be Flush Mounted Bingham and Taylor P200 NFG Test Station. Test Station is to be set flush with top of concrete shock collar.

b. Leads shall be a minimum of 150mm in diameter c. Hydrants shall be McAvity 67 or Mueller Century Model.

d. Hydrants to be left-hand open (counter clockwise).

e. Hydrant valves shall open in the same direction and be the same type as the mainline

f. Hydrants are to be supplied by the manufacturer as yellow.

g. Hydrants shall have a 150 mm barrel with two 63 mm hose connections and one 100 mm Stortz pumper port.

h. Hydrant flange to be installed 100 to 150mm above finished grade and shock collar. i. Hydrants shall have a 1m x 1m x 150mm shock collar cast in concrete. . A minimum of 2 metres clearance shall be provided around hydrants from trees,

pedestals, light standards, etc.

a. Water services shall be PEX cross linked higher pressure (polyethylene pipe must be labeled CAN/CSA-B1371) and a minimum working pressure of 160 PSI @ 23°C and mus be installed according to the Ontario Plumbing Code and Loyalist Township Standards.

Minimum pipe size is 25mm O.D. b. Main stops shall be the same size as the service pipe and shall have an AWWA tapered thread inlet and a compression joint outlet, 300 psi ball style valve. Main stops shall be Mueller Canada B25008N, Ford Meter FB1000-NL or Cambridge Brass 301NL. All curb stops shall be the same size as the service pipe and shall be compression joint inlet and outlet, no lead, 300 psi ball style valve. Curb stops shall be Mueller B-25209 series, Cambridge Brass 202 series or Ford B44 series. Self-draining (stop and drain) type curb & main stops are not permitted. All PEX water services shall be installed in accordance with Township W-16 standard and include a concrete support and electrical grounding tailing nuts on both sides for the connection of the tracer wire. All materials shall be

AWWA C800 and NSF 61 compliant. c. Bedding material shall be granular 'A' and at a minimum, be compacted to 150mm above

the water service. d. Curb stops shall be placed 300mm beyond property line

e. Water services to be without joints between main and property line regardless of length There shall be no buried ioints except at the streetline and at the service set. Anode to be installed as per W-16 on each service.

S EXISTING SANITARY MANHOLE **EXISTING HYDRANT** M EXISTING WATER VALVE **EXISTING WATERMAIN** EXISTING SANITARY SEWER **EXISTING STORM SEWER** EXISTING OVERHEAD HYDRO EXISTING GAS EXISTING UNDERGROUND BELL EXISTING SWALE C/L PROPOSED SWALE C/L — – — — – — PROPOSED STORM SEWER PROPOSED WATERMAIN PROPOSED SANITARY SEWER BENCHMARK CATCH BASIN DOUBLE CATCH BASIN DICB DITCH INLET CATCH BASIN ▼ STOP SIGN / AS NOTED → STREET SIGN

<u>LEGEND</u>

PROPOSED ASPHALT

PROPOSED MUP ASPHALT

PROPOSED DRIVEWAY REINSTATEMENT

PROPOSED CONCRETE

EXISTING STORM MANHOLE

STRAW BALE

EXISTING VEGETATION

EXISTING ELEVATION

PROPOSED ELEVATION

VEGETATION REMOVAL

BM1 - TOP OF HYDRANT NUT IN FRONT OF CIVIC 122 / 20 SAUL STREET. ELEVATION 126.092

BM2 - TOP OF HYDRANT NUT IN FRONT OF CIVIC 17 / 19 POTTER DRIVE. ELEVATION 125.259

ISSUED FOR TENDER MAR. 20, 2024 Revision/Issue



1329 Gardiners Road, Suite 210 Kingston, ON, Canada K7P OL8 613.634.9009 tel. 1.888.884.9392 fax

LOYALIST TOWNSHIP


POTTER DRIVE, CREIGHTON DRIVE, SOUTH AND MAIN STREETS RECONSTRUCTION


GENERAL PLAN


Designed by: Approved by: GEN


DECEMBER 2023 1:750























































REFER TO DRAWING G2













EMBEDMENT AND BACKFILL

ROCK EXCAVATION

OPSD 802.013








Structures


RH July 2015 SCALE NTS

DWG. W03-03-128









# **PRELIMINARY** NOT FOR CONSTRUCTION

ISSUED FOR TENDER MAR. 20, 2024 Revision/Issue



1329 Gardiners Road, Suite 210 Kingston, ON, Canada K7P OL8 613.634.9009 tel. 1.888.884.9392 fax.

LOYALIST TOWNSHIP


Scale:

N.T.S.

POTTER DRIVE, CREIGHTON DRIVE, SOUTH AND MAIN STREETS RECONSTRUCTION

DETAILS 5 WATER & SEWER DETAILS

Checked by:	Project No.
JH	
Approved by:	Drawing No.
KMN	
•	חר
	ו וו
	JH Approved by:



**PRELIMINARY** NOT FOR CONSTRUCTION

SECTION Z-Z

SECTION Z-Z

SECTION Z-Z

OPSD 604.010

ISSUED FOR TENDER MAR. 20, 2024 Revision/Issue



1329 Gardiners Road, Suite 210 Kingston, ON, Canada K7P OL8 613.634.9009 tel. 1.888.884.9392 fax.


LOYALIST TOWNSHIP

N.T.S.

POTTER DRIVE, CREIGHTON DRIVE, SOUTH AND MAIN STREETS RECONSTRUCTION

DETAILS 6 MISCELLANEOUS DETAILS

Drawn by:	Checked by:	Project No.
CGD	JH	
Designed by:	Approved by:	Drawing No.
KMN	KMN	
Date:	1	
DECEMBER 202	3	J IJĥ
Scale:		



cover to

Earth and 600mm in Rock

in uppermost layers.

to suit site conditions.

unless otherwise shown.

Smaller ducts shall be installed

3 Deviation from these maximum

values may be specified or

- - | - '- | - - | 1 - | - - | - -

V-DITCH

1275 ---

Nov 2021 Rev 3

OPSD 219.180

. . | . . | . | . | . .


Number of bales varies and shall suit ditch.

through barrier. Fill and compact gaps with loose straw.

2 Straw bales shall be butted tightly against adjoining bales and shaped to conform to

ONTARIO PROVINCIAL STANDARD DRAWING

STRAW BALE FLOW CHECK DAM




Mailbox

1.00

1.5m Access Ramp

per OPSD 310.010



THROUGH STREET

(AMHERSTVIEW AND ODESSA)
a. COLOUR: WHITE ON GREEN
b. FONT: CGTRIUMVIRATE B

c. LETTER SIZE:

d. EXTRUSION:

BOTTOM OF THE SIGN.

TERMINATING STREET CURB

┌─Marker tape

IN ROCK

URBAN STREET SIGN -

SIDEWALK

TRAFFIC SIGNS - TO BE HIGH INTENSITY GRADE REFLECTORIZED SHEETING (3m

STREET NAME SIGNS - TO LOYALIST TOWNSHIP - URBAN STANDARD

3. SIGNS TO BE ERECTED UPON COMPLETION OF BASE COURSE ASPHALT.

4. STOP BARS SHALL BE PROVIDED AT ALL STOP SIGNS UPON INSTALLATION OF

TRAFFIC CONTROL SIGNS TO BE MOUNTED AT A MINIMUM HEIGHT OF 2.0m

MEASURED FROM THE FINISHED ELEVATION AT THE BASE OF THE POST TO THE

6. LOCATION OF STREET SIGNS TO BE INSTALLED IN ACCORDANCE WITH ONTARIO

7. ON CORNERS WITH SIDEWALK ON THROUGH STREET, LOCATE SIGN POST 6.0m

ON CORNERS WITHOUT SIDEWALK ON THROUGH STREET, LOCATE SIGNPOST

3.0m BEHIND EDGE OF THROUGH STREET PAVEMENT AND 1.2m FROM BACK OF

BEHIND EDGE OF THROUGH STREET PAVEMENT AND 1.2m FROM BACK OF

9. ALL SIGNAGE TO BE INSTALLED AS PER OPSS 703 AND OPSD 990.110 ON

U-POSTS WITH A 1.5m LOWER POST AND A 3.0m UPPER POST BOLTED

MINIMUM TRENCH WIDTH FOR ONE LAYER AND TWO LAYER DUCT ARRANGEMENT

NUMBER OF 50 mm DUCTS

0 1 2 3 4 5 6 7 8 9 10 N/A 150 205 300 460 610 N/A N/A N/A N/A N/A N/A

150 255 460 610 610 N/A N/A N/A N/A N/A N/A

300 460 610 N/A N/A N/A N/A N/A N/A N/A N/A

300 460 460 610 610 N/AN/A N/AN/A N/AN/

IN EARTH

ONTARIO PROVINCIAL STANDARD DRAWING Nov 2013 Rev 1

DUCT INSTALLATION

IN TRENCHES

CGTRIUMVIRATE BOLD

-REGULATORY SIGN


-0.6m WIDE WHITE STOP BAR


SIGN PLACEMENT DETAIL

IN EARTH

OPSD 2101.01

300mm min all around layer of rip-rap







ALL DUCTS TO BE MANDRELLED AND CLEANED AFTER INSTALLATION, ALL DUCTS TO HAVE ½"
POLYESTER PULLING TAPE INSTALLED.
NUMBER OF CABLES/DUCTS AS WELL AS THEIR ARRANGEMENT WITHIN THE DUCT BANK AS SHOWN IS REPRESENTATIVE ONLY. DUCTS/CABLES MAY BE ADDED/OMITTED AND/OR RE-ARRANGED AS REQUIRED, PROVIDED THAT CLEARANCES AND SEPARATIONS ARE MAINTAINED. OVERALL TRENCHWIDTH TO CONFORM TO MUNICIPALITY REQUIREMENTS.

3 3 3 3 3

STANDARD STREET CROSSING DETAIL





NOTES:

1. ALL DIMENSIONS ARE AFTER CONSOLIDATION TO 100% STD. PROCTOR DENSITY

2. ALL DISTURBED AREAS TO BE REINSTATED WITH 100mm OF TOPSOIL AND SOD UNLESS SPECIFIED


3. SUBGRADE CONSTRUCTION TO BE COMPACTED TO 98% S.P.M.D.D. GRANULAR COURSES TO BE


4. JOINT SPACING

A) JOINTS EVERY 1.5m B) EXPANSION JOINTS AS FOLLOWS

- AT 6.0m ON STRAIGHT SECTIONS - AT 3.0m ON CURVED SECTIONS

- AT THE BEGINNING AND END OF CURVES BETWEEN ADJACENT STRUCTURES





# MAIN STREET MULTI-USE PATHWAY DETAIL

NOTES:

1. ALL DIMENSIONS ARE IN METRES OR MILLIMETRES UNLESS OTHERWISE


2. ALL DISTURBED AREAS TO BE REINSTATED WITH 100mm OF TOPSOIL AND

3. SUBGRADE CONSTRUCTION TO BE COMPACTED TO 98% S.P.M.D.D.

SOD UNLESS SPECIFIED OTHERWISE

4. ASPHALT WALKWAY SHALL BE CONSTRUCTED IN ACCORDANCE WITH OPSD 310.010

# **PRELIMINARY** NOT FOR CONSTRUCTION





1329 Gardiners Road, Suite 210 Kingston, ON, Canada K7P OL8 613.634.9009 tel. 1.888.884.9392 fax.

LOYALIST TOWNSHIP


N.T.S.

POTTER DRIVE, CREIGHTON DRIVE, SOUTH AND MAIN STREETS RECONSTRUCTION

DETAILS 7 MISCELLANEOUS DETAILS

Drawn by:	Checked by:	Project No.
CGD	JH	
Designed by:	Approved by:	Drawing No.
KMN	KMN	
Date:		חם
DECEMBER 2023		





# General 1. All construction traffic signals infrastructure must meet with current OPS, OPSD, ESA and

- all other governing authorities. 2. Non frangible bases to be used for traffic signals
- 3. All ducts to be finished as specified in contract documents
- 4. There must be ground plates located in the hand holes in all corners of the intersection
- along the power supply disconnect. 5. All hand holes to be 600mm x 600mm as per OPSD 2112.04
- 6. Contractor will be responsible for verifying all quantities
- 7. Pedestrian heads to be countdown type.
- 8. All traffic signal conduits shall be rigid PVC raceway conforming to CSA C22.2 No. 211.2-06 suitable for direct burial, concrete encasement or surface mounting.

# 9. Feed to power supply to be coordinated with hydro one.

- <u>Traffic Signal Cables</u>
  10. The Contractor shall supply and install sufficient fourteen (14) gauge colour coded traffic signal runner and riser cable, to accommodate all equipment and installation operations specified in this
- 11. The buried traffic signal cable shall meet the requirements of OPSS 2409.
- 12. All traffic signal cable shall be installed in the underground conduit system in the location shown on the Drawings. Runner cables for vehicle signal heads shall have 19 solid conductors. Runner
- cables for pedestrian signal heads shall have 12 solid conductors. 13. Each riser cable inside the pole, for the traffic signal head(s) and pedestrian head(s), shall be five
- (5) conductor and four (4) conductor respectively. Riser cables shall have stranded conductors. 14. The Contractor shall supply and install sufficient two (2) conductor, #14 AWG, extra low voltage cable, with shielded cover, from the pedestrian pushbutton(s) to the controller, through the underground conduit system.

3:1 (H:V) MAX SIDE SLOPE

Ground Wire

15. The Contractor shall supply and install a continuous #6 AWG TWU green, stranded copper ground wire through the entire main conduit system, including connection to the service. The ground wire shall be connected to all steel poles, the junction boxes on wood poles, the ground lug attached to the cover and frame in the handwells and the proposed ground rods in the handwells, in the location shown on the Drawings. The ground wire is not required outside the main conduit system

#### where there are no low voltage cables in the ducts. All ground wire splices shall be made with Thermit Weld connections or copper compression ground tap figure "C" connectors. 16. There shall be a separate continuous #6 AWG TWU green stranded copper ground wire from the controller to the service. The controller shall not be connected to the system ground.

- 17. A continuous #6 AWG TWU green, stranded copper ground wire shall be installed from the ground lug in the pole to the ground rod located adjacent to this pole.
- 18. This item shall include a continuous 2/0 bare, stranded copper ground wire which shall be installed from the service enclosure to the four ground rods located adjacent to this pole. 19. The green/yellow conductor in the traffic signal head and pedestrian signal head riser cable shall be connected to the system ground in a pole handhole and/or a junction box. A green conductor used as ground shall be tagged "ground" in the pole handhole and/or
- iunction box. 20.A continuous #12 AWG TWU green, stranded copper ground wire shall be installed from the proposed luminaire fixture to the ground lug in the luminaire pole.

\_\_ <u>250mm WTR</u>

**CONTROLLER PAD DETAILS** 

THIS DETAIL TO BE USED IN CONJUNCTION WITH OPSD'S

PLAN

- 100mm Conduit to HH1

75mm Conduit between Disconnect and Controller

- 50mm Conduit to HH1

⊢Finished grade

Traffic signal controller

where applicable

200mm high metal pedestal

Neoprene gasket, Detail `A`

75mm Conduit to supply point

21. The Contractor shall supply and install a 20 mm x 3.0 m copper clad ground rod in the location shown on the Drawings. The ground rod shall be driven into the bottom of the concrete handwell and into the ground adjacent to the service pole. The ground rod driven into the ground shall be buried so that the top of the ground rod is 300 mm below the finished grade and it shall be left uncovered until it has been inspected by the Contract Administrator. Connection to the ground rod shall be made with a Thermit Weld connector.

1-1/C #6 IGRD

1-19/C #14 SC 1-12/C #14 SC PED

2-2/C #14 PB

3 X 100mm DIA. DUCT

3-1/C #6 SL

1-1/C #6 IGRD 1-19/C #14 SC

2-2/C #14 PB

3-1/C #6 SL

1 (H:V) MAX SIDE SLOPE

TRAFFIC SIGNAL HEADS

1-12/C #14 SC PED

2 X 75mm DIA. DUCT

1-1/C #6 IGRD 2-19/C #14 SC 2-12/C #14 SC PED

2-2/C #14 PB

2 X 75mm DIA. DUCT

3-1/C #6 SL

#### Push Button Station 22.The Contractor shall supply and install an Accessible Pedestrian Signal Station as manufactured by Polara Engineering Incorporated, Model EN25BNO-PY, complete with mounting hardware.

#### 0.7m Octagonal Steel Combination Traffic Signal/ Luminaire Pole and Arm 3. The Contractor shall supply and install a Valmont West Coast Engineering, 8535 Series pole or an approved equal, in the location shown on the Drawings. The pole shall be octagonal hot dipped galvanized steel and shall be supplied complete with a pole cap and

- 24. The Contractor shall supply and install an Emergi-Lite/Powerlite Inc., Catalogue No. TR SMA-81 aluminium single member arm (or an approved equal) complete with all attachments and fittings for mounting on a metal. The mast arm shall be mounted as shown on the Drawings and in accordance with OPSD 2501.02.
- 25. The Contractor shall supply and install a 1.8 metre long elliptical aluminium luminaire mast arm. It shall be Utility Supply Specialists Manufacturing, TER-6-MA, with a minimum wall thickness of 0.188 inches or a SENTINEL Pole & Traffic Equipment Limited, RE-6-4188.

#### Concrete Pole Base

26. The Contractor shall construct a 762 mm diameter concrete pole base with anchorage assembly in the locations shown on the Drawings and in accordance with OPSD 220.01.

#### 27. The Contractor shall verify the bolt spacing with the pole manufacturer prior to construction

#### Traffic Signal Head (all 300mm lenses) Reflectorized

TC1 POWER SUPPLY 'A'

100A, 120/240Vι 1φ, 3W

CONTROL

CABINET

28. The Contractor shall supply and install a yellow/grey backed, polycarbonate, highway type,

1-1/C #6 IGRD

1-19/C #14 SC

2-2/C #14 PB

3-1/C #6 SL

\* 1-12/C #14 SC PED \* -

2 X 75mm DIA. DUCT

LED traffic signal head with a reflectorized backboard, cowl visors, 300 mm diameter red, amber and green LED signal lamps. All modules shall be labelled "ITE compliant" and labelled as such. The top entry hub shall be plugged with the device made for this purpose complete with a gasket. The bottom entry hub shall be plugged with the device made for this purpose but omitting the gasket.

#### 29. The traffic signal head shall be Federal Standard 595a, colour chip 13538 yellow and ASA-70 grey.

- 30. The reflectorized backboard shall be a yellow/grey backed, polycarbonate vehicle signal head backboard. Federal Standard 595a, colour chip 13538 yellow and ASA-70 grey backboards to be flexible poly and shall be provided with knock-out to allow installation with plumbizer. A 75mm reflective sheeting to be applied to the backboard along the perimeter of the front of the backboard in accordance with all manufacturer's recommendations
- 31. The 75mm reflective sheeting shall be as follows: 3M Diamond grade DG3 Reflective Sheeting Series 4000, product code 4081 (fluorescent yellow).
- 32.A traffic signal head with single point mounting (i.e., cushion hanger or plumbizer) must have stainless steel reinforcement plates. Cushion hanger mounting reinforcement shall be on the inside and outside of the red section. Plumbizer mounting reinforcement shall be in accordance with the manufacturer's specifications (i.e., inside and outside of the amber section or outside of the red and amber sections).

#### Pedestrian Signal Head

S

33. The Contractor shall supply and install a yellow two section polycarbonate Automatic Signal/Eagle Signal LED countdown pedestrian signal head with a 300 mm square lens complete with cutaway visors and a minimum 260 mm high numeric display, or an approved equal.

- 34. The top lens shall be a GELcore square, bimodal LED pedestrian signal, Model Number D12PAC MS:4 or an approved equal. The bottom lens shall be a GELcore square, LED countdown signal, Model Number D12PAD MS:4 or an approved equal.
- 35. The LED countdown signal display shall be set up to operate during the pedestrian clearance interval.
- 36. The LED countdown pedestrian signal head shall be installed in the location shown on the Drawings.

EX. ASPHALT DRIVEWAY

EX. ASPHALT

#### SIGNALS LEGEND

—G>

EX. CONC. S/W

EX. 1.5m CONC. S/W

EX. ASPHALT

EX. CONC. S/W

EX. 1.5m CONC. S/W

TRAFFIC CONTROLLER AND POWER SUPPLY

ELECTRICAL HANDHOLE

EX. ASPHALT

EX. ASPHALT 0 OH OH OH OH OH OH OH OH OH

EX. CONC. S/W

**GROUND PLATE** 

PEDESTRIAN PUSH BUTTON PEDESTRIAN SIGNAL HEAD (COUNTDOWN TYPE) ---LIGHT FIXTURE

HIGHWAY SIGNAL HEAD WITH BACKBOARD AND MAST ARM (ALL 300mm LENSES)

WIRING REQUIREMENTS Traffic signal cable (19/C # 14 SC) Traffic signal heads (5/C # 14 RISER) Pedestrian heads (4/C # 14 RISER) Pedestrian push buttons (2/C # 14 SHIELDED), extra low voltage cross-linked polyethylene cable (OPSS 623) Ground wire (1/C # 6) (OPSS 609) Power (1/C # 6) Low Voltage Single Conductor RWU90

Street lighting (1/C # 6) Low Voltage Single Conductor RWU90 — – — – — PROPOSED STORM SEWER



— — — PROPOSED WATERMAIN

<u>LEGEND</u>

PROPOSED ASPHALT

PROPOSED DRIVEWAY REINSTATEMENT

PROPOSED CONCRETE

**EXISTING HYDRANT** 

**EXISTING GAS** 

—— PROPOSED SWALE C/L

EXISTING SWALE C/L

PROPOSED SANITARY SEWER

EXISTING WATER VALVE

EXISTING WATERMAIN

**EXISTING SANITARY SEWER** 

EXISTING OVERHEAD HYDRO

EXISTING UNDERGROUND BELL

EXISTING STORM SEWER

EXISTING STORM MANHOLE

S EXISTING SANITARY MANHOLE

PROPOSED MUP ASPHALT

☐ CATCH BASIN DOUBLE CATCH BASIN

DICB DITCH INLET CATCH BASIN ▼ STOP SIGN / AS NOTED

#### → STREET SIGN EXISTING VEGETATION

VEGETATION REMOVAL STRAW BALE

EXISTING ELEVATION

PROPOSED ELEVATION

# **PRELIMINARY**

BM1 - TOP OF HYDRANT NUT IN FRONT OF CIVIC 122 /

20 SAUL STREET. ELEVATION 126.092 BM2 - TOP OF HYDRANT NUT IN FRONT OF CIVIC 17 / 19 POTTER DRIVE. ELEVATION 125.259

RI	ISSUED FOR TENDER		MAR. 20,
No.	Revision.	/Issue	Dat


1329 Gardiners Road, Suite 210 Kingston, ON, Canada K7P OL8 613.634.9009 tel. 1.888.884.9392 fax

LOYALIST TOWNSHIP

POTTER DRIVE, CREIGHTON DRIVE, SOUTH AND MAIN STREETS RECONSTRUCTION

PEDESTRIAN TRAFFIC SIGNALS DETAIL

Drawn by:	Checked by:	Project No.
CGD	JH	
Designed by:	Approved by:	Drawing No.
KMN	KMN	
Date:	1	$\Box$ DU
DECEMBER 2023		<b>∣ 114</b>



#### 50mm Flex ENT between Disconnect and Controller POWER SUPPLY AND CABINET NOTES The Contractor shall supply and install equipment for the power supply on the service pole in the location shown on the Drawings and in accordance with OPSD 2130.011, 2440.010, 2440.030, 2440.04, 2440.050, 2440.060, and 2440.061.

The power supply cabinet assembly shall be Type 1, 120/240 volt, 100A, 1 Phase, complete with:

100 Amp main circuit breaker

2m X 1.5m Concrete pad OPSD-2514.02

Power Supply and Disconnect


- 60 Amp traffic signal circuit breaker
- 15 Amp relamp breaker 4 - 15 Amp branch breakers

### The Contractor shall coordinate the hydro feed cable with the Local Hydro Authority.

The Contractor shall also supply and install the hydro feed cable for the traffic signals from the proposed power supply to the proposed controller through the underground conduit system. The feed cable shall be single conductor, stranded copper, low voltage cable, rated 600 volts. Low voltage cables shall meet the requirements of OPSS 604. The cable shall be sized so as to satisfy the voltage drop requirements of the electrical/electronic equipment and shall not exceed 5%.

The Contractor shall supply and install an 8 phase Econolite cabinet, to Loyalist Township specifications. The Contractor shall install an 8-phase solid state microprocessor-based controller with a 12 position back panel set up to operate on 2, 4, 6, 8 phases and in a semi actuated mode. Phases 1, 3, 5, 7 will not be used for the initial installation. The controller shall provide for pedestrian timing on 2 phases and vehicle timing on 4 phases. The controller shall be programmable to start up in Phase 2 and Phase 6 amber.

Pedestrain signal timing to be configured for Walk Interval (W) of 7 seconds and Flashing Don't Walk Interval (FDW) of 10 seconds for a complete Pedestiran Signal Cycle of 17 seconds.



MANUFACTURER